IRONWOOD CIVIL CONTRACTORS

Change Order Request

CHANGE ORDER NO.
CO 9

DATE
10/02/2025

PROJECT
Westfield Retail Pad Site

PROJECT NO.
IW-7740

OWNER
Westfield Commercial Partners

CONTRACTOR
Ironwood Civil Contractors

SCOPE OF CHANGE: Remove unsuitable soils and import structural fill at building pad. Unforeseen subsurface condition: organic clay encountered at 3 ft, not identified in the geotechnical report.

Description	Qty	Unit	Rate	Amount
Excavate and haul unsuitable soil	640	CY	18.50	11,840.00
Import and compact structural fill	640	CY	32.00	20,480.00
Geotechnical testing	1	LS	2,350.00	2,350.00
	Total			$34,670.00

Time Extension: 2 weeks
Awaiting Owner approval.